



1225 Tri State Parkway, Ste 510
Gurnee, IL 60031
Ph: 847.245.8450
Fax: 847.245.8590
www.kieferusa.com

KIEFER USA PROPOSAL

Project: Tiffin Columbian High School Outdoor Track
Tiffin, OH
Date: October 12th, 2023
Scope: Synthetic Running Track Surfacing

Pricing is Based on Information Provided to Kiefer USA Regional Sales Manager – Aaron Goebbel.

Area	Scope of Work	Cost
Outdoor Track	331823 – Synthetic Running Track Surfacing <ul style="list-style-type: none"> Furnish and Install 11mm Base Mat Rubberized System Paved in Place. Base Mat to be Installed at Track Oval, Chutes, High Jump, and Event Runways. Apply 2mm Black Champion Structural Spray Track Surface in Two Coats. Surrounded Areas to be Covered with Plastic to Prevent Overspray or Damage During the Construction Process. Includes NFHS Painted Track Line Markings and Events as Needed. 	
	TOTAL LUMP SUM PRICE	\$ 332,130.00
	2% TIPS CO-OP PRICE	\$ 6,650.00
	P&P BOND PRICE	\$ 3,580.00

Conditions:

- Any permits or licenses required by the township, county, province or any other governing body having jurisdiction over construction is the responsibility of the Customer or General Contractor.
- Unforeseen Work Site Conditions: If concealed or unknown conditions, including, but not limited to, surface, subsurface and/or site environmental conditions, which affect in whole or in part the performance of the Work are encountered, then Kiefer USA shall stop work and give written notice thereof to appropriate party (e.g., Owner, General Contractor, Construction Manager, etc.). The Agreement (e.g., costs, prices, schedule, etc.) shall be adjusted accordingly.
- The asphalt subsurface subfloor must be cured a minimum of 28 days prior to installation of the running track surface. Flooding the asphalt or verification of slope and levelness can and should be performed prior to full cure.
- Prior to our arrival on the site, the asphalt subsurface must be tested for planarity; Mondo requires not more than 1/8" deviation within a 10'-0" radius. Any repair work necessary to correct surfaces to meet the above requirements must be done by others. Floor preparation work done by Kiefer USA is limited to smoothing of minor hairline cracks, small holes, and other minor imperfections not exceeding 1/8" deep or wide.

Kiefer USA can provide additional information on any of the above items upon request.

Payment Terms: 50% Deposit Upon Signing, 40% Upon Material Delivery, 10% Upon Completion.
Financing Options Are Available.

This proposal-pricing letter is valid for 30 days from the date of proposal, as noted above. If the above pricing is acceptable, please sign below, and return to our corporate office with your purchase order as soon as possible, so we may proceed as per the project requirements. If you have any questions regarding this proposal, please contact Michael Mattea at 847.245.8450, ext. 125.



Respectfully Submitted,



Aaron Goebbel
Regional Sales Manager
Kiefer USA



Michael Mattea
Project Estimator
Kiefer USA

Accepted By:

Name	Date
Company	Title

.....